

ADDENDUM NO. 1
FOR
GOOSE POND TRAIL EXTENSION
FOR
THE TOWN OF SCOTTSBORO, AL
RTP PROJECT NO. 15-RT-54-10

April 10, 2017

TO: ALL PLAN HOLDERS AND INTERESTED PARTIES

SUBJECT: Plans, Specifications, and Contract Documents are hereby amended, modified, and changed as follows:

- I. Reference Contract Documents, Part II - Bid, Bid Schedule
 - A. Replace the existing Bid Schedule, Page II-2 with the attached revised Bid Schedule, which adds Item No. 14 – Concrete Wheel Stops and Parking Lot Striping.

- II. Reference Contract Documents, Part V – Special Conditions, Paragraph 43.E.- Bid Item Descriptions, Page V-18
 - A. Add Paragraph 43.E.12 to the Bid Item Descriptions as follows:
 12. *Bid Item No. 14 – Concrete Wheel Stops and Parking Lot Striping as shown on Plans*
 - a. *Complete labor, material and equipment for wheel stops and striping including, but not limited to, concrete wheel stops, striping, layout, installation, anchoring, clean-up and all related items for a complete installation meeting the intent of the Contract Documents.*
 - b. *Payment shall be lump sum for complete installation.*

- III. Reference Plan Sheet No. 3. Detail A/2
 - A. Remove the word (N.I.C.) from Detail A/2. The park benches are included the Contract.

IV. Reference Plan Sheet No. 4, Detail A/4 - ADA Compliant Picnic Table

A. Add the following to the existing note:


*Table to be Smimilar and Equal to 238H Series, All MIG Welded Frame,
End Access. (Ultrasite Cat. No. 27, Page 31)*

THIS ADDENDUM ISSUED THIS 10TH DAY OF APRIL 2017.

LADD ENVIRONMENTAL CONSULTANTS, INC.

Adam J. Lea

Adam Lea, P.E.



BIDDER agrees to perform all the work described in the Drawings, Bid Documents and Specifications for the following unit prices or lump sum. **NOTE:** BIDS shall include sales tax and all other applicable taxes and fees. (See SPECIAL CONDITIONS, PART V, for explanation of Bid Items.)

BID SCHEDULE

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
1.	Clearing, Grubbing and Site Preparation	1	LS	\$	\$
2.	Dense Grade Base (Installation Only, Material Provided by Owner)	1,200	TON		
3.	Riprap (Installation Only, Material Provided by Owner)	500	TON		
4.	Geotextile Underlayment for Riprap	454	SY		
5.	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B, Approximately 220 #/sq.yd.	209	TON		
6.	6' – 0" Wide Concrete Walkway Including Toe Wall, Footing and Aluminum Handrail	240	LF		
7.	15" CHDPE Storm Water Pipe for Walking Path Cross Drains	35	LF		
8.	18" CHDPE Storm Water Pipe for Walking Path Cross Drains	40	LF		
9.	11" x 18" Concrete Arch Storm Water Pipe for Parking Lot (Installation Only, Material Provided by Owner)	80	LF		
10.	Pressure Treated Sign Support	1	LS		
11.	Perforated Metal Anchored Park Benches	4	EA		
12.	ADA Double-Sided Picnic Table	1	EA		
13.	Erosion Control Measures, Topsoil and Grassing	1	LS		
14.	Concrete Wheel Stops and Parking Lot Striping as shown on Plans	1	LS		

TOTAL BID: \$ _____