

ADDENDUM NO. 2
FOR
WASTEWATER TREATMENT PLANT SCREENING, LIGHTING AND ELECTRICAL
UPGRADES
CWSRF PROJECT NO. CS010396-06
FOR
THE CITY OF FORT PAYNE, AL

October 30, 2017

TO: ALL PLAN HOLDERS AND INTERESTED PARTIES

SUBJECT: Plans, Specifications, and Contract Documents are hereby amended, modified, and changed as follows:

- I. Reference Part VI – Technical Specifications, Division No. 11 – Equipment, Section 11332 – Self Cleaning Automatic Perforated Plate Fine Screen
 - A. Page 11332-9, Paragraph 3.07 Schedule
 - i. Add the following as 3.07 A. 12.
 12. Downstream water level at max flow = 25.7”.
 - ii. Add the following as 3.07 A. 13.
 13. Upstream water level (maximum allowable) = 44”.
 - iii. Add the following as 3.07 A. 14.
 14. Headloss (maximum allowable @ 15% blinding) = 18.3”.
- II. Reference Plan Sheet 9, Detail F
 - a. Change Modified Stop Gate Height from 3’-6” to 3’-8” (i.e. from 6” to 4” from top of channel).

III. Reference Plan Sheet E-2

A. Add Note #2 under Oxidation Ditch Motor Starter at MCC:

- i. The new 75HP RVSS shall fit in existing starter space (18"). Contact Eaton (Patrick Hecht at 770-548-4153) for pricing. Unit shall be provided complete with all new Eaton components, including UL label.

THIS ADDENDUM ISSUED THIS 30th DAY OF October, 2017.

LADD ENVIRONMENTAL CONSULTANTS, INC.


Caleb Lea, P.E.

