

ADDENDUM NO. 1
FOR
RE-BID DOWNTOWN SUMMERVILLE STREETScape
WASHINGTON STREET
FOR
THE CITY OF SUMMERVILLE
AND
THE CHATTOOGA COUNTY COMMISSION
PROJECT NO. PI#0010702

AUGUST 22, 2018

TO: ALL PLAN HOLDERS AND INTERESTED PARTIES


SUBJECT: Plans, Specifications, and Contract Documents are hereby amended, modified, and changed as follows:

- I. Reference Contract Documents, Part II – Bid Schedule, Additive Alternate No. 1, Page II-4
 - A. Replace Pages II-4 and II-5 with the Revised Additive Alternate No. 1 and Additive Alternate No. 3 Bid Schedule.

- II. Reference Plan Sheets 1, 3 – 7, 13, 14-16, 24, 26, 27, 29, 30 and 31
 - A. Replace referenced Plan Sheets with the revised sheets.

THIS ADDENDUM ISSUED THIS 22nd DAY OF AUGUST 2018.

LADD ENVIRONMENTAL CONSULTANTS, INC.


Adam J. Lea, P.E.



BASE BID SCHEDULE

(Continued)

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
653-3501	Thermoplastic Skip Traffic Stripe, 5", White	30	GLF		
653-6004	Thermoplastic Traffic Striping, White	9	SY		
653-6006	Thermoplastic Traffic Striping, Yellow	29	SY		
654-1003	Raised Pavement Markers, TP3	23	EA		
685-2000	Blast Cleaning PC Concrete Structures	2,682	SF		
700-7000	Agricultural Lime	1	TN		
700-8100	Fertilizer Nitrogen Content	200	LB		
708-8000	Plant Topsoil	329	CY		

TOTAL BASE BID: \$ _____

ADDITIVE ALTERNATE NO. 1

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
205-0001	Unclassified Excavation	217	CY		
207-0203	Found Backfill Material, Type II	41	CY		
550-1180	Storm Drain Pipe, 18", H 1-10	71	LF	\$	\$
550-1204	Storm Drain Pipe, 24", H 1-10	131	LF		
550-3000	Elliptical Pipe – 29" x 18" RCP	107	LF		
603-2036	STN Dumped Rip Rap, TPI, 36 In.	33	SY		
603-2181	STN Dumped Rip Rap, TP3, 18 In.	32	SY		
603-7000	Plastic Filter Fabric	65	SY		
668-1100	Catch Basin, GP 1	1	EA		
668-2100	Drop Inlet, GP 1	3	EA		

TOTAL ADDITIVE ALTERNATE NO. 1: \$ _____

ADDITIVE ALTERNATE NO. 2

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
700-9300	Sod	1,109	SY	\$	\$

TOTAL ADDITIVE ALTERNATE NO. 2: \$ _____

ADDENDUM NO. 1

BID SCHEDULE
(Continued)

ADDITIVE ALTERNATE NO. 3

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
702-0542	Tree – Lagerstroemia Indica (Crepe Myrtle)	4	EA	\$	\$

TOTAL ADDITIVE ALTERNATE NO.3: \$ _____

ADDITIVE ALTERNATE NO. 4

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
754-5000	Benches	9	EA	\$	\$

TOTAL ADDITIVE ALTERNATE NO. 4: \$ _____

ADDITIVE ALTERNATE NO. 5

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
754-4000	Waste Receptacle Unit – (Metal)	2	EA	\$	\$

TOTAL ADDITIVE ALTERNATE NO. 5: \$ _____

ADDITIVE ALTERNATE NO. 6

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
766-7020	Irrigation System (Complete)	LS	LS	\$	\$

TOTAL ADDITIVE ALTERNATE NO. 6: \$ _____

ADDITIVE ALTERNATE NO. 7

GDOT ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
999-001	Decorative Banner/Flower Poles with Irrigation Tubing	9	EA	\$	\$

TOTAL ADDITIVE ALTERNATE NO. 7: \$ _____