

ADDENDUM NO. 2
FOR
COLLINSVILLE MUNICIPAL PARK SOFTBALL COMPLEX
FOR
THE TOWN OF COLLINSVILLE
LWCF PROJECT NO. 16-LW-1032

FEBRUARY 15, 2019

TO: ALL PLAN HOLDERS AND INTERESTED PARTIES

SUBJECT: Plans, Specifications, and Contract Documents are hereby amended, modified, and changed as follows:

I. Reference Part VI Technical Specifications, Division 2, Page 02206-1, Paragraph 1.05, Qualificatons

A. Replace Paragraph 1.05 with the following:

1. Final ballfield surface and subsurface construction shall be by an installer with a minimum 5 years documented experience with sitework using laser grading.

II. Reference Plan Sheet No. 1

A. Contractor may use chert as a fill material provided that it is not within 4 inches of the finished surface. Material in the top 4 inches may include topsoil, infield mix, on-site soil or other materials free of rocks, depending on the location.

B. All areas that are to be grassed require topsoil and seeding. Sodding is not required in any location on the project.

III. Reference Attachment "B," Geotechnical Report.

A. Testing as referenced in Section 4.4, Structured Fill, is hereby required as one test per 20,000 SF of area for ballfield construction.


B. Minimum 85% compaction shall be required for all ballfield areas.

C. For proof rolling, a truck weighing no less than 25,000 pounds will be required.

D. It is the intent of the project to utilize on-site soils for fill material.

THIS ADDENDUM ISSUED THIS 15th DAY OF FEBRUARY, 2019.

LADD ENVIRONMENTAL CONSULTANTS, INC.



James Payton, P.E.

