### **ADDENDUM NO. 4**

#### **FOR**

# CONTRACT NO. 1 – WASTEWATER MAINTENANCE BUILDING FOR

## THE WATERWORKS, SEWER AND GAS BOARD OF THE TOWN OF SECTION

### **OCTOBER 7, 2024**

TO:

ALL PLAN HOLDERS AND INTERESTED PARTIES

SUBJECT:

Plans, Specifications, and Contract Documents are hereby amended, modified, and changed as follows:

- I. Reference Part VI Technical Specifications, Division No. 13 Special Construction, Section 13121 Pre-Engineered Metal Buildings, Page 13121-2, Paragraph 1.04.F.
  - A. Revise Paragraph 1.04.F as follows:
    - F. Roof Slope: Three (3) inches in twelve (12) inches.
- II. Reference Contract Documents, Part II, Bid, Page II-8 (Addendum No. 1)
  - A. In Explanation of Bid Form, Paragraph F.4. Change the description to read as follows:
    - 4. Bid Item No. 4 Settling Tank and Piping
      - a. Complete labor, materials and equipment for installation of a settling tank, manholes, piping, and all associated building, sanitary sewer, discharge piping including, but not limited to, excavation, grading, precast concrete tank, manholes, piping, clean-up,, seeding and all related items for a complete installation meeting the intent of the Contract Documents.
      - b. Basis of payment shall be lump sum for complete installation.

- B. <u>General Notes</u>: Any other items not clearly identified in the Explanation of Bid Items shall be included in Bid Item No.1 Maintenance Building (Complete).
- III. Reference Addendum No. 3, Part VI Technical Specifications, Division No. 7 Thermal and Moisture Protection, Section 07213 Bolt and Blanket Insulation
  - A. Revise Page 07213-2, Paragraph 3.03.B. as follows:
    - B. Roof Insulation (No Suspended Ceiling): R-19; white vinyl faced.

THIS ADDENDUM ISSUED THIS 7<sup>TH</sup> OF OCTOBER 2024.

LADD ENVIRONMENTAL CONSULTANTS, INC.

James Payten 10.07

James Payton, P.E